

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LIMITED  
PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna-801505

Ph: 0612- 2251622, 2252553, 2252542; Fax No.- 0612-2250325

Email Id.- [vpmu.pur@gmail.com](mailto:vpmu.pur@gmail.com)

PDP: PUR: FBD: 8204

DATE- 11.02.2025

72

Dear Sir,

We are interested for fabrication of shed at Chhapra C.C.

Details of item required and scope of work is enclosed herewith.

If interested to do this work kindly submit your rate to our office in sealed envelope latest by 25.02.2025. Your rate must be F.O.R Chhapra C.C.

Thanking You

Yours faithfully

  
Manager(MM)

Materials Required for New Top Shed Work shed L- 70' X W- 18'=1260 sqrfeet  
 And Side wall L-70' X H-6'=420 sqrfeet Total area 1680 Sqr feet.at- Chhapra.

S.I. No.	Description & Specification	Qty.	Unit
1	Ms 3" pipe square pipe 75 mm (Thick- 3.5mm) 7 Lenth X 32 kg per lenth	224	KG
2	Ms 2" pipe square 50 mm (Thickn- 3.00 mm ) 25+4=29 Lenth X 16 kg per lenth	464	KG
3	Ms 1.5" pipe square pipe 33 mm (Thick- 1.5 mm ) 22+7=29 Lenth X 12 kg per lenth	348	KG
4	Ms 1" pipe square pipe 25 mm (Thickness- 1.5 mm ) 5 lenth X 8 kg	40	KG
5	MS Flat patti 2"	10	KG
6	Durasine sheet colour cotted TATA 0 45 thick (10' x 3'.6")	70	Pic.
7	TaTa Agrico Screw ( 55 mm)	500	Pic.
8	TaTa Agrico Screw ( 25 mm)	200	Pic.
9	Electrod belding Rod 10 No.3 Pkt	3	Pic.
10	Hexsaw Bled 4"	25	Pic.
11	Labour job for MS Rafter making for Roofing & Cladding MS Sqare Pipe Cutting, Hosting, Welding & Framed (Note :- all Material Providing for PDP) ( Top Shed Area- 70' x 18' =1260 sqf )and Side wall (L-70 X H-6=420 Sqft) Total area =1680 Soft	1680	sqf