

# VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

## PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

An ISO 22000:2005 Certified Organisation

Phone 0612-2252553,2252542, 2251622, Fax 2250325

E.mail:vpmu.pur@gmail.com

GST no. 10AAAV8463B1ZV

### Short Tender Notice


PDP:PUR:FBD: 8840

Dated: 27.02.2025

Sealed tenders are invited from civil contractors registered with Building Construction works Department, Rural Works Department, Water Resource Department, Government of Bihar OR registered with COMFED in suitable class for the civil work as given below :-

Sl no.	Name of Work	Estimated Cost (In Rs.)	Amount of EMD (In Rs.)	Cost of BOQ ( In Rs.)	Time of Completion
	<b>Civil construction work for fixing of Kota Stone on the verandah and stair near Milk Packaging Hall in Bulk Milk Chilling cum Packaging Unit at Chhapra. The details scope of work as per BOQ attached herewith</b>	96495.00	1930.00	500.00	30 days

- (1) Tender document can be obtained from the Cashier at office (Patna Dairy Project), VPDUSS Ltd during office hours OR it may be downloaded from website – [www.patnadairy.org](http://www.patnadairy.org) up to **15.03.2025 at 3.00 pm**. Downloaded BOQ must be accompany with DD of BOQ Cost. DD of any nationalized bank shall be submitted in favour of “**Vaishal Patliputra Dugdh Utpadak Sahkari Sangh Ltd.**”, Payable at **Patna**
  - (2) Contractors who down load the tender and those who purchase the **tender / BOQ** directly from office at Patna Dairy Project, both will send their completed tender in a sealed envelope **through registered post or through courier to Purchase section at Patna Dairy Project address.**
  - (3) Last date of receipt of completed tender – **16.03.2025 up to 3:00 pm. Tenders received after due date & time shall not to be considered.**
  - (4) Date of **opening all received tenders-17.03.2025 at 3:00pm** in the presence of the tenders of their authorized agent in the office of Patna Dairy Project, VPMU.
  - (5) Tenders received after due date & time shall not be considered.
- Undersigned reserves the right to extend the dates OR cancel the tender.

  
Managing Director

## Measurement Sheet Cum Bill Of Quantity (BOQ)

For Civil Construction work for fixing of kota stone on the verrandah and stair near milk packaging hall in BULK MILK CHILLING CENTRE CUM MILK PACKAGING UNIT, CHAPRA

### (GENERAL ABSTRACT OF COST)

Sl. No./ Code. SOR-22	Description of Work	Unit	Length	Breadth	Depth	Qty.	Rate (Rs.)	Amount (Rs.)
15.1	Demolishing lime concrete and disposal of material within 50 metre lead	cum	14.00	5.00	0.075	5.25	340.5	1787.625
11.26	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete. Base with 1:1:1 (1 lime : 1 surkhi : 1 coarse sand) / 1:4 (1 cement : 4 coarse sand)							
11.26.1	Flooring 20 to 25 mm thick	sqm	14.00	5.00	0	70.000	1252.70	87689.00
11.27	Kota stone slabs 20 mm thick risers of steps skirting. Dado and pillars laid on 12 mm (average thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete. Details of cost for 10 sqm							
11.27	Kota stone skirting (H=.150m)	sqm	10.1	0.15	0	1.515	1334.90	2022.37
<b>TOTAL SUM (A)</b>								<b>89711.37</b>

	Carriage of materials	UNIT	QUANTITY	RATE	AMOUNT
I	SONE SAND	cum	1.71407152	737.45	1264.042
II	CEMENT	mt	0.457696	492.75	225.5297
III	DIFFERENCE OF COST				
IV	CEMENT(SARAN)	mt	0.457696	166.51	76.21096
<b>TOTAL SUM OF CARRIAGE CHARGES (B)</b>					<b>1565.78</b>
<b>TOTAL SUM = (A + B)</b>					<b>91585.70</b>
<b>TOTAL SUM(A+B) IN ROUND OFF = C</b>					<b>91586.00</b>
<b>ADD 5.36 % GST AS PER PWD NOTIFICATION ON C = D</b>					<b>4909.01</b>
<b>FINAL TOTAL BILL SUM OF = (C + D)</b>					<b>96495.01</b>
<b>TOTAL BILL AMOUNT AFTER ADDING GST</b>					<b>96495.00</b>

NINETY SIX THOUSAND FOUR HUNDRED AND NINETY FIVE ONLY WITH G.S.T.

S.NO.	I AM AGREE TO DO THIS WORKS:	IN %	IN WORD
1	ON THE BOQ RATE		
2	BELOW THE GIVEN RATE (IN %)		
3	ABOVE THE GIVEN RATE (IN %)		

SIGNATURE OF CONTRACTOR

SIGNATURE OF MANAGER (Engg.)

*(Signature)*  
Aditya Saurav