

**VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD
PATNA DAIRY PROJECT**

Feeder Balancing Dairy Complex, Phulwarisharif, Patna - 801505

Phone 0612-2252553,2252542, 2251622, Fax 2250325

E.mail:vpmunin@gmail.com

REMINDER

PDP/PUR/1725

Dated-18/06/15

SHORT TENDER NOTICE

Quotation are invited for Water Supply & Electrification work etc. at Milk Chilling Centre , Chapra. The detail scope of work is attached herewith for ready reference in Annexure I .

Interested parties may submit their quotation latest by 30/06/2015 by 5.00 PM in a sealed envelope addressed to Managing Director , VPDUSS Ltd. , Patna superscribing on the envelope 'Water Supply & Electrification work at Milk Chilling Centre, Chapra ' .


AGM(Purchase)

Enclosure : As above

Note : 1) The rates should be all inclusive FOR Site

2) For any clarification bidder may contact Manager,Engg. , FBD
before quoting

CC : Manager,FBD/CFE
: Incharge , HCC/BCC
: Incharge,Accts,Hq
: Notice Board , FBD
: patnadairy.org

Annexure –I
Scope of work :

Water Supply Arrangement -

Sl No.	Particulars	Qty	Unit	Rate	Value
1	Providing & fixing 15 mm C.I. Pillar Cock	2	Nos		
2	Providing & fixing Pillar Cock				
a)	20 mm dia Brass				
b)	25 mm dia Brass				
3	Making holes in wall for laying PVC pipe & restoring the same as per direction	2	Nos		
4	Supplying & laying PVC pipe(Standard) with all fitting & fixtures as per direction				
a)	20 mm dia (approx)	15	mtr		
b)	25 mm dia (approx)	30	mtr		
c)	32 mm dia (approx)	10	mtr		
5	Supply of ISI marked SYNTEX water tank , Capacity 750 ltr	1	Nos		
	Total				
	Applicable Taxes				
	TOTAL				

Submersible Pump 4" x 2" Bore well

Sl No.	Particulars	Qty	Unit	Rate	Value
1	Usha 100 mm PVC Pipe	80	Rft		
2	Usha 50 mm PVC Pipe	200	Rft		
3	50 mm PVC	24	Rft		
4	Reducing socket 4" Dia	1	No		
5	Clamp 4" dia	1	No		
6	PVC 4" dia socket	4	No		
7	GI Pipe 4" dia	3	Rft		
8	Solvent top 200 gm	2	Nos		
9 a)	Submersible pump (single 1 HP 4" size control panel box and starter with 25 mtr wire	1	nos		
b)	Supplying of labour , tools for boring	1	Lot		

	charge upto 2401 and filling at submersible pump complete as per direction				
c	Supply of Labour tools & Tackles for boring above 240 ‘				
	Total				
	Applicable Taxes				
	TOTAL				

Electrification Work

Sl No.	Particulars	Qty	Unit	Rate	Value
1	Wiring of light/fan/exhaust fan point with 1.5 sqmm PVC Insulated copper cable in conduit as required	20	Nos		
2	Wiring for 5 pin 5-15 Amp plug point with 1.5 mm PVC Insulated copper conduit cable including providing & fixing 3 pin 5-15 Amp socket on switch board (in conduit) wiring system & 15 Amp Piano type switch earthing the third pin pointer as required with copper conductor wire	3	nos		
3	Circuit wiring with 2 x 105 sqmm PVC Insulated copper conductor single core cable in ressed PVC conduit as required	20	mtr		
4	Wiring for Sub-main with 2 x 6 sqmm PVC Insulated copper conductor single core cable in recessed PVC conduit as required	11	mtrs		
5	Supplying & drawing/fixing 224 mm dia bore copper conductor wire loop earthing as required	10	mtr		
6	Supplying of Sheet steel MCB distribution board on surface complete job	1	lot		
	Total				
	Applicable Taxes				
	TOTAL				