

**VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD**

**PATNA DAIRY PROJECT**

**Feeder Balancing Dairy Complex, Phulwarisharif, Patna - 801505**

**Phone 0612-2252553,2252542, 2251622, Fax 2250325**

**E.mail:vpmunin@gmail.com**

**PDP/PUR/ 2138**

**Dated-09/07/2015**

**SHORT TENDER NOTICE**

Quotation are invited for Sarmera Milk Chilling Centre from interested parties having license from Electricity Board , may submit their offer for providing Electrical connection with material & labour as per estimate of Assistant Electrical Engineer , Biharsharif. You may like to submit your offer to the undersigned latest by 25/07/2015.

The detail scope of work is attached herewith for ready reference in Annexure .

  
**AGM(Purchase)**

**Enclosure : As above**

**Note : 1) The rates should be all inclusive FOR Site**

**2) For any clarification bidder may contact Manager,Engg,FBD**

**CC : Manager,FBD/CFE**

**: Incharge , HCC/BCC/Maner/Chapra**

**: Incharge,Accts,Hq**

**: Notice Board , FBD**

**: patnadairy.org**

S.B.P.D.C.L.

The estimate for new DSS and line for milk chilling centre Samsera under Samsera section under P/S/D Asthawan under deposit Head.

S.No.	Name of material	Quant.	Rate	Amount
1.	Psc Pole 40kg	2 No	3000=00	6000=00
2.	Psc Pole 20kg	2 No	2451=00	4902=00
3.	63KVA dist. Transformer	1 No	119313=00	119313=00
4.	Transformer AB switch base	2 set	2887=00	5774=00
5.	HG fuse base channel	1 pair	2692=00	2692=00
6.	Transformer Belting angle	1 set	1265=00	1265=00
7.	C.Lamp for support of all channel	6 pair	83=00	498=00
8.	11KV V cross arm / string bracket with clamp	3 Nos	501=00	1503=00
9.	11KV Top Bracket and clamp	3 Nos	119=00	357=00
10.	G.I stay set complete with wire	6 Nos	1418=00	8508=00
11.	11KV Disc insulator with fitting	6 Nos	484=00	2904=00
12.	11KV insulator with pin	16 Nos	119=00	1904=00
13.	ACSR Rabbit conductor	0.5 km	26622=84	13311=42
14.	Earthing material	2 No	1508=00	3016=00
15.	G.I. Earth wire red	25kg	47=00	1175=00
16.	L.T. Distribution Bus bar angle	1 Nos	230=00	230=00
17.	11KV AB switch 200 amp	1 set	14585=00	14585=00
18.	L.T Pin insulator with pin	10 Nos	87=00	870=00
19.	HG Fuse set 11KV	1 set	6651=00	6651=00
20.	M/S Nuts & bolts (diff size)	50 kg	99=00	4950=00

Attsted  
Bl. 72  
5/7/2015  
Y. Acc

(A) Cost of material	200408=42	203206=50	203206=50
(B) cont + T&P @ 4%	8016=33	8128=26	
(C) Transstation cost @ 4%	8016=33	8128=26	
(D) Labour cost @ 10% x 2.25	45091=89	45721=46	
(E) Supervision charge @ 15%	39229=94	39777=67	
	<u>300762=91</u>	<u>304962=15</u>	

Checked & Vetted  
Shail

Account Officer  
Electric Supply Division  
Biharsharif  
26/6/15

Say No - 304962=00 only  
15/06/15  
AEE/Asthawan

Loknath Prasad  
15/06/15  
JEE/Prasad