

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna-801505
Ph: 0612- 2251622, 2252553, 2252542; Fax No.- 0612-2250325
Email Id.- vpmu.pur@gmail.com

PDP: PUR: FBD 7152

DATE-08.01.2025

Dear Sir,

S.No.	Item	Specification	Quantity
1)	Steam Line Insulation Work at new curd section.		
2)	Chilled Waterline Insulation new curd.		
3)	SS Pipeline Insulation for new curd section.		

Details of work specification, quantity etc as per enclosed **Annexure – 01**.

If interested for work kindly submit your quotation latest by **20.01.2025**.

Thanking You

Yours faithfully



Manager(MM)

Annexure-01

Pipeline insulation work in new curd section along with supply of materials & labour charges at FBD.

Sl.No.	Name of the work	Details:				
		1. M.S. Pipelines				
A.	Steam line insulation work: Insulation of steam line pipe with glass wool, 22 gauge chicken wire mesh with glass wool and cladding with 24 gauge Al sheet with material and labour.	Sl.No.	Size	Qty	Unit	Remarks
		01	20 NB	50	Feet	± 10%
		02	50 NB	60	"	± 10%
		03	80 NB	48	"	± 10%
		2. M.S. Bends				
		01	20 NB	14	Nos.	± 10%
		02	50 NB	10	"	± 10%
B.	Chilled waterline Insulation work: Insulation of chilled water line pipe with thermocol of 3.0" thickness, 20kg/m3 density with 8525 grade bitumen, cladding with 24 gauge Al sheet complete with material and labour.	1. G.I. Pipelines				
		Sl.No.	Size	Qty	Unit	Remarks
		01	65 NB	300	Feet	± 10%
		02	100 NB	40	"	± 10%
		2. G.I. Bends				
		01	65 NB	30	Nos.	± 10%
		C.	SS Pipeline Insulation work: Insulation of SS Pipeline line thickness with 25 MM with armaflex complete with all materials density-40kg/m3 and labour.	1. S.S. Pipelines		
Size	Qty			Unit	Remarks	
51 MM	600			Feet	± 10%	
2. S.S. Bends						
51 MM	40			Pcs.	± 10%	


 21.12.24
 Manager (Engg.)