

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LIMITED
PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna-801505

Ph: 0612- 2251622, 2252553, 2252542; Fax No.- 0612-2250325

Email Id.- vpmu.pur@gmail.com

PDP:PUR:FBD:

9382

DATE- 19.03.2025

REMINDER

Dear Sir,

We are interested for fabrication of shed at Chhapra C.C.

Details of item required and scope of work is enclosed herewith.

If interested to do this work kindly submit your rate to our office in sealed envelope latest by 31.03.2025. Your rate must be F.O.R Chhapra C.C.

Thanking You

Yours faithfully


Dy. Manager(MM)

Materials Required for New Top Shed Work L- 70' x W – 18' = 1260 sqrfeet
And Side wall L- 70' x H- 6' = 420 sqrfeet. Total Area 1680 Sqr feet at Chhapra

Sl. No.	Description & Specification	Qty.	Unit
1	Ms 3" pipe square pipe 75 mm (Thickness – 3.5mm) 7 length x 32 kg per length	224	Kg.
2	Ms 2" pipe square pipe 50 mm (Thickness – 3.00mm) 25+4=29 length x 16 kg per length	464	Kg.
3	Ms 1.5" pipe square pipe 33 mm (Thickness – 1.5mm) 22+7 = 29 length x 12 kg per length	348	Kg.
4	Ms 1" pipe square pipe 25 mm (Thickness – 1.5mm) 5 length x 8 kg	40	Kg.
5	MS Flat patti 2"	10	Kg.
6	Durasine sheet colour cotted TATA 0.45 thick (10' x 3'.6")	70	Kg.
7	Tata Agrico Screw (55mm)	500	Pic
8	Tata Agrico Screw (25mm)	200	Pic
9	Electrod belding Rod 10 No. 3 Pkt	03	Pic
10	Hexsaw Bled 4"	25	Pic
11	Labour job for MS Rafter making for Roofing & Cladding MS Square Pipe Cutting, Hosting, Welding & Framed (Note – all materials providing for PDP) (Top Shed Area – 70' x 18' = 1260 sqf) and Side wall (L – 70 x H – 6 = 420 Sqft.) Total area = 1680 Sqft.	1680	Sqft.