

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

VPDUSS-SOP-8.5.1.2-01.F02

PDP: PUR: FBD: 623

Dated: 25/4/26

Dear sir,

We are interested for Electrical Connection SBPDCL for extension of 11 KV HT Line & Installation of 11/0.4 KV 100Kva DSS for new site at **Rasbagh BMC, Barh, Patna.**


Details scope of work and required material in as per estimate of Electrical Engineer Sub Division, Barh is enclosed herewith.

If interested to work kindly submit your rate in sealed envelope lasted by **10.05.2026.**

Encl: as above

Thanking you

Yours faithfully


Dy. Manager (MM)

South Bihar Power Distribution company Ltd

Installation of 11/0.4Kv 100KVA DSS at new site at Rasbagh BMC, Barh, Patna

Sn	Material Description	Unit	Qty
1	100 KVA Distribution Transfer	nos	1
2	PSC Pole 300 KG, 9 Meter	nos	2
3	ACSR DOG Conductor	km	0.2
4	11 KV AB Switch 200 A	set	1
5	11 KV Lightning Arraster	set	1
6	Clamp for Lightning Arraster	nos	3
7	Danger Board	nos	2
8	Back Clamp for Danger Board	nos	2
9	11 KV Pin Insulator with GI Pin	set	3
10	11 KV Disc Insulator with H/W Fitting	set	6
11	11 KV HG FUSE SET withn support clamp	set	1
12	Side stay set Clamp	set	4
13	Stay set with Wire (Complete Set)	set	4
14	Gay Insulator	nos	4
15	Tranformer Top Channel	set	1
16	AB Switch mounting Channel	set	1
17	Support clamp for Transformer Top Channel	Pair	2
18	Tranformer Base Channel	set	1
19	Transformer side Base Channel	set	1
20	Support clamp for Transformer side base	Pair	2
21	Transformer H G Fuse set Channel	set	1
22	Support Clamp for HG Fuse Channel	Pair	2
23	Transformer Fastening angle for DSS	set	1
24	Back Clamp for Tr. Fastening angle	nos	2
25	P G Clamp for DOG Conductor	nos	6
26	GI Wire	kg	20
27	Nuts and Bolts	kg	20
28	GI Strip for Earthing work	Mtr	20
29	Sundries	L/S	