

**VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD.**

*(Patna Dairy Project)*

*Feeder Balancing Dairy COMPLEX, PHULWARISHARIF, Patna-801505)*

*An ISO 22000:2005 Certified Organization)*

*Phone: 2252553, 2252542, 2251622, Fax:0612-2250325*

*E-mail: [Vpmunin@gmail.com](mailto:Vpmunin@gmail.com) / [vpmu.enggg@gmail.com](mailto:vpmu.enggg@gmail.com)*

*GST no.-10AAAV8463B1ZV*

# **TENDER DOCUMENT**

**[For Civil Constriction work of (6) Six Platforms of size 14.0 feet X 13.0 feet x 2.0 feet (H) from Ground level for installing Prefabricated Whole Day Milk Booths at 6 (Six) different Locations in Patna District]**

**Prepared by**

**Vaishal Patliputra Dughdh Utpadak Sahkari Sangh Ltd  
Patna Dairy Project, Fulwarisharif, Patna  
801505**

**Cost of tender = Rs 750.00  
(Rs Seven Hundred Fifty only)**

# **VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD.**

(Patna Dairy Project)

Feeder Balancing Dairy COMPLEX, PHULWARISHARIF, Patna-801505)

An ISO 22000:2005 Certified Organization)

Phone: 2252553, 2252542, 2251622, Fax:0612-2250325

E-mail: [Vpmunin@gmail.com](mailto:Vpmunin@gmail.com) / [vpmu.engg@gmail.com](mailto:vpmu.engg@gmail.com)

GST no.-10AAAV8463B1ZV

## **Tender Notice**

**VPMU: Engg: Sat NISCHAY: 7663**

**Date:-04-03-2023**

Sealed tenders are invited from civil contractors registered with Building Construction Works Department, Rural Works department, Water resource Department, Government of Bihar OR registered with COMFED in suitable class for the civil work as given below:-

Sl no	Name of work	Estimated cost(In Rs )	Amount of EMD (In Rs)	Cost of BOQ(In Rs)	Time of Completion
1	Civil construction work of Platforms of size 14.0 feet X 13.0 feet x 2.0 feet (H) from Ground level at different locations in Patna district for installing prefabricated whole day milk booths as per BOQ & specification (total - 6 Nos)	3,75,576 .0	7,550.00	750.00	Total 6 (Six) months

- (1) Tender document can be obtained from the office of In-Charge (Engg), Patna dairy project, VPDUSS Ltd during office hours OR it may be downloaded from website - [www.patnadairy.org](http://www.patnadairy.org) up to 04-04-2023 (Tuesday) at 3.00 PM.
- (2) Contractors who down load the tender and those who purchase the tender /BOQ directly from office of I/C (Engg), both will send their completed tender in a sealed envelope through registered post or through courier to I/C (Engg) at above address.
- (3) Last date of receipt of completed tender - 05-04-2023 (Wednesday) up to 3.0 PM. Tenders received after due date & time shall not be considered.
- (4) Date of opening all received tenders - 06-04-2023 (Thursday) at 3.00 PM in the presence of the renderers or their authorized agents in the office of Patna Dairy Project, VPMU.
- (5) Tenders received after due date & time shall not be considered.

Undersigned reserves the right to extend the dates OR cancel the tender.

**Managing Director**

## **VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD.**

(Patna Dairy Project)

Feeder Balancing Dairy COMPLEX, PHULWARISHARIF, Patna-801505)

An ISO 22000:2005 Certified Organization)

Phone: 2252553, 2252542, 2251622, Fax:0612-2250325

E-mail: Vpmunin@gmail.com / vpmu.engg@gmail.com

GST no.-10AAAV8463B1ZV

### **(A) Description of civil work to be done :-**

Civil Construction work of Six (6) platforms each of size 14.0 feet X 13.0 feet x 2.0 feet (H) from Ground level at following six (6) locations In Patna District is to be done as per specification & BOQ.

Sl no	Name of blocks of land allocated	Locations where platform for installing pre fabricated Whole Day Milk Booth (WDMB will be Constructed.
1	MANER	Block office campus (near MANDIR)
2	BIHTA	Near BIHTA Auto stand
3	DULHIN BAJAR	Near DHARMSHALLA (Near SHIO MANDIR)
4	PALLIGANJ	Govt Bus Depot Campus
5	NAUBATPUR	NAUBATPUR BAJAR, (Near Potato market)
6	ATHMALGOLA	Near YATRISHED (High School)

### **(B) Prequalification terms / Eligibility Criteria**

- (1) Contractors registered with Building Construction Department, / Rural works Department / Water Resources Department, Govt. of Bihar or COMFED in suitable class **shall have to submit along with tender ,the proof of execution of two civil works of similar nature (Building construction work) during last four (4) years except year of tender. Contractors registered with COMFED are exempted from submission of proof of execution of the civil works.**
- (2) Also Contractors shall submit following documents duly attested by any gazetted officer along with tender:-
  - (a) Copy of GST registration certificate,
  - (b) Copy of PAN registration certificate
  - (c) Copy of Payment certificate of civil works executed during last 4 years in reference to clause (1) above. Please mention WO no with date in payment certificate.
- (3) Up- date Income Tax Clearance certificate (ITR) of last three (3) years [2019-20, 2020-21 & 2021-22]
- (4) Contractors shall submit the acceptance of all the terms & conditions of the tender on their letter head with Signature & seal along with the tender.
- (5) The contractor must submit the copy his registration no. /category of Registration and office in which registered distinctly.
- (6) All the documents should be enclosed with tender and submitted in a sealed envelope.

## **VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD.**

(Patna Dairy Project)

Feeder Balancing Dairy COMPLEX, PHULWARISHARIF, Patna-801505)

An ISO 22000:2005 Certified Organization)

Phone: 2252553, 2252542, 2251622, Fax:0612-2250325

E-mail: Vpmunin@gmail.com / vpmu.engg@gmail.com

GST no.-10AAAV8463B1ZV

### **(C) General Conditions of the Contract for work**

1. Sealed tenders on prescribed Bill of Quantity (BOQ) [to be eventually drawn in P.W.D. Form – F-2] will be received by Dy. Manager (Engg) cum I/C (Engg) from registered Contractors as per prequalification terms of Building Construction Department, / Rural works Department / Water Resources Department, Govt. of Bihar or COMFED in suitable class.
2. The Estimated Amount (BOQ Value) is of Rs. 3, 75 576.00 (Three LAKH seventy Five Thousand Five Hundred Seventy Six only) for all six (6) platforms at the rate of Rs 62,596.00 each (Rs Sixty Two Thousand Five Hundred Ninety Six only).
3. Cost of tender (BOQ) for the work can be obtained as per tender notice from the office of Dy. Manager (Engg) cum I/C (Engg) Patna Dairy Project during working hours on payment of Rs. 750.00 as cost of (BOQ) tender (Rs Seven Hundred Fifty only non refundable ).
4. For obtaining BOQ directly contractors shall make a request to I/C (Engg) who will forward the same to Manager (A/C), FBD for deposition of cost of tender, thereafter BOQ will be issued by I/C (Engg).
5. The bill of quantity (BOQ) and tender documents will also be obtained by downloading the same from website [www.patnadairy.org](http://www.patnadairy.org) .. But in this case tenderers will have to attach the demand draft of Rs 750.00 towards the cost of tender in Favor of the VPDUSS Ltd while submitting the sealed tender.
6. **Earnest Money Deposit –**  
Tenderers shall deposit earnest money of Lump sum Rs 7, 550.00 (Rs Seven Thousand Five Hundred Fifty only ) [Being calculated at the rate of Rs. 100/- (One hundred) for every Rs. 5000/- or part on the amount of estimated cost of Rs 3, 75,576.00.  
The earnest money is to be submitted /deposited in shape of NSC duly pledged in-favour of the VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD  
OR  
In shape of Bank draft in favour of VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD- payable at Patna shall also be accepted. EMD & Cost of tender shall be enclosed with tender in sealed envelope.
7. **The earnest money of the successful tenderer which accompanies the tender will be forfeited in case he (tenderer) declines to sign the agreement / to deposit balance security within ten days of being called upon to do so after the acceptance of his tender.**

## **VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD.**

(Patna Dairy Project

Feeder Balancing Dairy COMPLEX, PHULWARISHARIF, Patna-801505)

An ISO 22000:2005 Certified Organization)

Phone: 2252553, 2252542, 2251622, Fax:0612-2250325

E-mail: Vpmunin@gmail.com / vpmu.engg@gmail.com

GST no.-10AAAV8463B1ZV

8. All other information if any, can be obtained through application from the office of the Dy. Manager (Engg) cum I/C Engg VPDUSS Ltd.
9. The rates should be inclusive of all materials. The tenderer should also indicate the rebate they will allow if levy cement @ Rs. NIL per bag either in full or part is arranged for the work by VPDUSS Ltd.
10. The plan, elevation and specification for the work can be seen at the office of the Dy. Manager (Engg) cum I/C Engg VPDUSS Ltd during the working hour and day time.
11. Tenderers who will obtain the tender document with BOQ by downloading from website [www.patnadairy.org](http://www.patnadairy.org) attach cost of tender and earnest money while submitting the tender in a sealed envelope.

### **(D) SPECIAL CONDITION FOR THE WORK**

Sl no	Special conditions of the Contract for the work
1	Managing Director, VPDUSS Ltd shall be the competent authority and he reserves the right rejects any or entire received tenders without assigning any reason thereof.
2	No claim will be entertained due to idle labour and/any or and other cause.
3	levy cement if supplied by the Federation will be at the rate noted below :- a) Cement ---- NA b) Place of delivery-- NA
4	The contractor will have to provide huts for the labourers at his own cost and will have to observe all labour rules including observance of the minimum labour waged
5	After completion of work, the sites of the work will have to be cleared off from all rubbish and un-used materials for which no extra payment will be made.
6	<u>Time of completion</u> of the work is Six (6) months for construction of all six (6) platforms from the date of issue of work order. However the contractor may quote his own time of completion. But Managing Director, VPMU shall have the sole description to accept the same.
7	The contractor employing motor vehicles should follow rules with regard to motor vehicles.
8	The contractor employing motor vehicles should follow rules with regard to motor vehicles.

## **VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD.**

(Patna Dairy Project

Feeder Balancing Dairy COMPLEX, PHULWARISHARIF, Patna-801505)

An ISO 22000:2005 Certified Organization)

Phone: 2252553, 2252542, 2251622, Fax:0612-2250325

E-mail: Vpmunin@gmail.com / vpmu.engg@gmail.com

GST no.-10AAAV8463B1ZV

<b>Sl no</b>	<b>Special conditions of the Contract for the work</b>
<b>9</b>	<b>For excess consumption of the union's materials over the actual requirement, recovery will be made at panel rate i.e. double of issue rate.</b>
<b>10</b>	<b>Only <u>kiln burnt</u> bricks will have to be used by the contractor in construction of work.</b>
<b>11</b>	<b>The contractor will be liable to pay compensation under the work-man's Act for accident or less of life, if any</b>
<b>12</b>	<b>The contractor will be have to maintain site order book on the site of work exhibit able to inspecting officers any time on demand.</b>
<b>13</b>	<b>All works shall be carried out in workmanship like manner and as per standard specification of the VPMU / COMFED.</b>
<b>14</b>	<b>The Managing Director, VAISHAL PATLIPUTRA DUGDH UTPADAK SANGH Ltd (VPMU) reserves the right on <u>distribution of work among several contractors.</u></b>
<b>15</b>	<b>Two percent (2%) Income Tax, (Five percent) 5% Security and Sales Tax/GST (Good Service Taxes) as per rule will be deducted from all payments (Gross amount).</b>
<b>16</b>	<b>The tenderers are presumed to have inspected the site and acquainted him with the local condition of the work and no claim due to ignorance these conditions and also site conditions will be entertained.</b>
<b>17</b>	<b>No claim will be entertained for fluctuation of the rates of labour/materials and carriage at any stage of work under progress.</b>
<b>18</b>	<b>Items of work beyond agreement shall not be executed by the contractor, if this becomes a necessity, written order of Engineer In-charge should be obtained before taking up such works. Such items shall ordinarily be paid at schedule of rate. However, Contractor may prefer a claim before taking up such works and await decision of rates by the competent authority.</b>
<b>19</b>	<b>Quantity of work may increases or decrease in accordance with the order of Engineering In- charge (E/I).</b>
<b>20</b>	<b>Contractor will assist supervision of work, measurement and verification of bills by the officers of the VPDUSS Ltd (VPMU) and will mend good any items damaged in course of inspection, measurement and verification of work.</b>
<b>21</b>	<b>Foundation trench shall have to be kept dry during the execution of work &amp; de-watering can be ordered by the E / I if necessary.</b>
<b>22</b>	<b>Only LAFARGE, A.C.C PRISM, L &amp; T &amp; GRASIM / Ultra tech cement will be used.</b>

**VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD.**

(Patna Dairy Project

Feeder Balancing Dairy COMPLEX, PHULWARISHARIF, Patna-801505)

An ISO 22000:2005 Certified Organization)

Phone: 2252553, 2252542, 2251622, Fax:0612-2250325

E-mail: Vpmunin@gmail.com / vpmu.engg@gmail.com

GST no.-10AAAV8463B1ZV

Sl no	Special conditions of the Contract for the work
23	<p><b><u>PAYMENT TERMS :-</u></b></p> <p>(a) The bill will be submitted by the Contractor once in a month for substantial quantity of work done. However VPMU is not bound to make monthly payment for works considerably lower than warranted by the proportionate time.</p> <p>(b) The final bill shall be submitted by the contractor within three months of physical completion of the work or within one month of the date of the final certificate of completion furnished by the Engineer In Charge whichever is earlier.</p>
24	<p><b><u>Liquidated damages / Delay Penalty:-</u></b></p> <p>For delay in completion of the work beyond the stipulated completion time of Six( 6) months, a deduction at the rate of half percent (1 / 2 %) per completed week of delay day shall be made from your Running Account (RA) bills of those works which are completed beyond completion time of six (6) months. The penalty deduction under Liquidated Damage (LD) Clause should not exceed 10 % (Ten percent) of the total ordered / contract value.</p>
25	<p><b><u>Extension of Time:-</u></b></p> <p>However, extension of the time for completion of the work, on the ground of having been unavoidably hindered in the execution of work OR on any other ground other than <b><u>force majeure</u></b> Contractor may make request in writing to Managing Director / Engineer In-charge immediate after the date of start of the hindrance. It will be the sole discretion of the Managing Director to grant time extension. If time extension is granted penalty deducted und LD clause will refunded</p>

I/C (Engg)

VPDUSS Ltd, Patna Dairy Project

**BILL OF QUANTITY (BOQ) / ABSTRACT OF COST**

S.no	SOR-2022	Description of works	Unit	Qty	Rate	Amount (Rs)
1	P-98/2.8.1	Earth work in excavation in foundations trenches Or drains (Not exceeding 1.5 M width or 10 SQM on plan) including dressing of sides & ramming of bottom, lift up to 1.5 M including getting out the excavated soil& disposal of surplus excavated soil as directed within a lead of 50 M	CUM	3.8	360.7	1370.660
2	P-101/2.28	Supplying& filling in plinth with local sand& under floors including watering ,ramming, consolidating& dressing all complete	CUM	4.5327	287.3	1302.244
3	P-192/11.72	Providing designation 100 A one brick flat soling, joints filled with local sand including cost of watering, taxes ,royalty all complete as per building Specification & direction of E/I.	SQM	20.18	283.3	5716.994
4	P-109/5.1.3	Providing& laying in position specified grade of RCC excluding the cost of centring,& shuttering ,finishing& reinforcement-All work up to plinth level with Nominal mix (1:2:4)	CUM	2.3718	4232.4	10038.406
5	P-110/5.9.1	Centring & shuttering including strutting, propping etc And removal form for foundation ,footings base of columns etc for mass concrete	SQM	2.922	211.6	618.295
6	p-120/6.1.14A	Brick work with bricks of class designation 100 A in foundations & plinths in cement mortar of 1:6	CUM	3.327	4829.9	16035.807
7	P-208 /13.11.3	Cement plaster in course sand12 mm of cement plaster of mix 1:5	SQM	26.1	146.8	3831.48
8	P-112/5.22.7A	Reinforcement for RCC work including straightening, cutting ,bending, placing in position& binding all complete TMTC- 500= 8 mm dia				6338.209
9	<b>Sum of 1 to 8</b>					<b>45252.096</b>



10	<b>Sum carried forward from page – 1</b>				<b>45252.096</b>
11	<b>CARRIAGE CHARGE</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount (Rs)</b>
	<b>CALCULATION</b>				
(i)	<b>Bricks</b>	<b>% 0 Nos</b>	<b>2293.849</b>	<b>1053.35</b>	<b>2415.33</b>
(ii)	<b>Local sand</b>	<b>CUM</b>	<b>4.835</b>	<b>262.77</b>	<b>1270.49</b>
(iii)	<b>Course sand</b>	<b>CUM</b>	<b>2.262</b>	<b>1258.31</b>	<b>2846.29</b>
(iv)	<b>Stone chips</b>	<b>CUM</b>	<b>2.11019</b>	<b>2987.7</b>	<b>6304.04</b>
(v)	<b>Cement &amp; Reinforcement</b>	<b>MT</b>	<b>1.1432</b>	<b>518.09</b>	<b>592.17</b>
12	<b>Sum of [11 - (i) to (v) ]</b>				<b>13428.32</b>
13	<b>Difference in Carriage of materials</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount (Rs)</b>
(i)	<b>Bricks</b>	<b>% 0 Nos</b>	<b>2293</b>	<b>1590.87</b>	<b>3648.09</b>
(ii)	<b>Cement</b>	<b>MT</b>	<b>1.06</b>	<b>252.66</b>	<b>267.93</b>
14	<b>Sum of [13 - (i) &amp; (ii) ]</b>				<b>3916.02</b>
15	<b>Total Estimated cost of one (1) platform for one WDMB[Sum of 10,12 &amp; 14 ]</b>				<b>62596.40</b>
16	<b>Total estimated cost for 6 (Six) platforms for 6 WBMBs (15 X6)</b>				<b>3,75,576.00</b>
<b>Rs Three LAKH Seventy Five Thousand Five Hundred Seventy Six only</b>					

**I agree to do / execute the civil construction work of platforms**

**(6 nos) required for whole day milk booths**

<b>1</b>	<b>On the given BOQ rate /estimate</b>	
<b>2</b>	<b>Percentage above the given BOQ rate /estimate</b>	
<b>3</b>	<b>percentage below the given BOQ rate /estimate</b>	

**Signature of I/C (Engg) with seal**

**Signature of Contractor with seal**

