

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmunin@gmail.com

PDP: PUR: 6398

Dated: 06.03.2019

SHORT TENDER NOTICE

Sealed Tender is invited from experienced party for **Supply & Laying of cables at FBD, Patna**. The details scope of work is attached herewith as per Annexure- I.

Interested parties may submit their quotation latest by 25.03.2019 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna superscribing on the top of the envelope Tiles **"Supply & Laying of cables at FBD, Patna"**.


Incharge(MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notice Board, FBD, CFF, HCC
Patnadairy.org

Supply & Laying of cables at FBD, Patna

Sl No.	Description of work	Unit	Qty.
1.	PVC insulated aluminium conductor 3.5 core, Armored cable of 300 sq mm – (2 x 150 M)=300 M with cable, Havels/Gloster Finolex/equivalent make Al lugs of 300 sq mm- 24 pcs for phase & 12 Pcs for 150 sq mm neutral, cable glnds set -6 set including supply of GI cable trays of 12" size = 100M	Meter	300
2.	Aluminum cable lugs for 300 sq mm for phase	Pcs	24
3.	Aluminum cable lugs for 150 sq mm for Neutral	Pcs	10
4.	Cable glands suitable for 300 sq mm cable	Set	8
5.	GI cable tray of 12" size	Meter	80
6.	Laying of cable 300 sq mm underground complete with all labour for digging trench, laying cable, putting sand & brick separator and then soil covering	Meter	15 x 3=45
7.	Laying of GI cable trays of 12 inch size over channel support to be provided by PDP including fitting of cable lugs for phases & neutral & fitting cable glands	Meter	80
8.	Laying of cable 300 sq mm over cable trays laid on channel support all complete work	Meter	3 x 85= 255