

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmunin@gmail.com

PDP: PUR: 2456

Dated: 31.07.2019

SHORT TENDER NOTICE

Sealed Tender is invited from experienced party for **Civil work in Drainage Line from new Softener plant to ETP Drain Chamber at HCC**. The details scope of work is attached herewith as per Annexure –I

Interested parties may submit their quotation latest by 10.08.2019 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna superscribing on the top of the envelope "Drain Line work of HCC from new Softener plant to ETP Plant".



Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC
Patnadairy.org

**Civil work in Drainage Line from new Softener plant to ETP
Drain Chamber at HCC**

Sn	Description of work	Unit	Qty
1.	Earth work in Excavation	CUM	68.03
2.	Local Sand Filling	CUM	3.68
3.	Flat Brick Soling	SQM	49.09
4.	PCC (1:2:4)	CUM	4.88
5.	Brick work in chamber with Mortar in 1:6 (1cement: 6 coarse sand)	CUM	3.8
6.	Plaster & Punning with mortar(1:4)	SQM	11.2
7.	15mm cement plaster on outer Face of chamber with mortar (1:6)	SQM	11.7
8.	RCC M20(1:1.5:3)	CUM	0.83
9.	Reinforcement - 08mm	kg	37.71
10.	Shuttering	SQM	15.4
11.	Laying of non-pressure NP2 class (light duty) R.C.C. pipe of 300 mm dia	M	70

