

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505
Phone – 0612-2252553, 2252542, 2251622, Fax-2250325
Email :- vpmu.pur@gmail.com

PDP: PUR: 2427

Dated: 31.07.2019

SHORT TENDER NOTICE

Sealed Tender is invited from experienced party for **Civil work for Drain work for disposal of waste water of Powder Plant and Procurement section Bathroom at HCC Plant, Hajipur**. The details scope of work is attached herewith as per Annexure –I & Annexure –II.

Interested parties may submit their quotation latest by 10.08.2019 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles **“Drain work at HCC Plant”**.



Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notice Board, FBD, CFF, HCC
Patnadairy.org

Construction work open Drain & 10" dia PVC pipe and Chamber at –Powder Plant South side HCC, Hajipur

Sn	Description of work	Unit	Qty
1.	Earth work	M ³	57.942
2.	Local Sand Filling	M ³	4.96
3.	Flat Brick Soling (100 A brick)	M ²	36.04
4.	RCC (1:1.5:3)	M ³	3.6736
5.	Brick work (1:6)	M ³	8.81
6.	Shuttering (Footing)	M ²	10.62
7.	Plaster & Panning	M ²	75.713
8.	Reinforcement - 08mm	kg	124.295
	10mm	kg	127.318
9.	10" Dia PVC Pipe fitting & Fix 43.50 mtr x 3.281 =142.72 R.F.	R.F.	142.72

Annexure -II

Construction work Chamber & Drain Line 6" dia PVC pipe at- South Boundry wall and old Toilet HCC, Hajipur

Sn	Description of work	Unit	Qty
1.	Earth work	M ³	21.1
2.	Local Sand Filling	M ³	6.88
3.	Flat Brick Soling (100 A brick)	M ²	23.80
4.	PCC (1:2:4)	M ³	2.38
5.	RCC (1:1.5:3)	M ³	1.10
6.	Brick work (1:6)	M ³	5.66
7.	Shuttering (Footing)	M ²	30.56
8.	Plaster & Panning	M ²	19.72
9.	Reinforcement - 08mm	kg	61.818
10.	6" Dia PVC Pipe fitting & Fix.	Mtr	56.0