

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 7744

Dated: 20.03.2020

21

SHORT TENDER NOTICE

Sealed Tender is invited from experienced party for **Construction of three Dump Pits at Fatuha, Ekangarsarai and Biharsharif Chilling Centre**. The details scope of work is attached herewith as per **BOQ**.

Interested parties may submit their quotation latest by 31.03.2020 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles **"Dump Pits at Fatuha, Ekangarsarai and Biharsharif Chilling Centre"**.


Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notice Board, FBD, CFF, HCC
Patnadairy.org

Bill of Quantities(BOQ)

WORK:- Civil work in construction of three new dump pits at Fatuha, Ekangarsarai and Bihar Sharif chilling centres

SOR 2018	NAME OF WORK	UNIT	QTY.	RATE	AMOUNT
p-185/15.3	Demolishing RCC work including stacking of steel bars and disposal of unserviceable material within 50 meters lead.	CUM	1.176	1172.7	1379.095
p-72/2.6.1	Earth work in surface excavation for all type of soil exceeding 30 cm in depth exceeding 1.5m in width as well as well as 10 sqm on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m .Disposed soil to be leveled and neatly dressed	CUM	11.581	279.1	3232.257
P-75/2.28	Supplying and filling in plinth with local sand and under floors including watering,ramming,consolidating and dressing complete	CUM	1.176	238.6	280.594
P-153/11.73	providing designation 100A one brick Edge soling joints filled with local sand including cost of watering, taxes,royalty all complete as per building specification and direction of E/I	SQM	7.84	439.8	3448.032
P-83/5.1.2	Providing and laying in position 1:1.5:3(1 cement :1.5 coarse sand :3 graded stone aggregate 20mm nominal size) in plateform and floor base excluding the cost of centering,shuttering,finishing and reinforcement upto plinth level	CUM	1.693	4902.3	8299.594
P-93/6.1.14A	Brick work with bricks of class designation 100A in superstructure UPTO plinth level with cement mortar 1:6(1 cement : 6 coarse sand) upto plinth level	CUM	3.8	4799.2	18236.960
P-167/13.12.4	15 mm cement plaster 1:6(1 cement : 6 coarse sand) on exterior of partition wall	SQM	25.84	145.5	3759.720
P-167/13.26	Neat cement punning	SQM	25.84	38.6	997.424
P-86/5.22	Reinforcement for RCC work including straightening,cutting,bending,placing in position and binding all complete				
P-86/5.22.7A	TMTC-500-8 mm bars	Kg	83.546	77.4	6466.460
P-84/5.9	CENTRING AND SHUTTERING including				

P-84/5.9.3	For dump pit floor edge	SQM	1.400	362.6	507.640
P-84/5.9.5	For lintels,beams and bands	SQM	4.48	335.3	1502.144
Details attached	Carriage charge		Rs		13494.486
TOTAL ESTIMATED COST (of one dump pit at Fatuha)=					61604.406
TOTAL ESTIMATED COST(SAY)=					61604
ESTIMATED COST(of similar nature of dump pit at Ekangarsarai)					61604
ESTIMATED COST(of similar nature of dump pit at Biharsharif)					61604
TOTAL ESTIMATED COST (of all the three dump pits at Fatuha,Ekangarsarai and Bihar Sharif CCs)=					184812
Rs One Lakh Eighty Four Thousand Eight Hundred Twelve only					

I AGREE & READY TO DO THIS WORK

1.0	ON THE GIVEN B.O.Q RATE	%	
2.0	ABOVE THE B.O.Q RATE(PRESENT)	%	
3.0	BELOW THE B.O.Q RATE(PRESENT)	%	

Note:Quoted rate should neither be less than 10% of total amount of BOQ nor it should be more than 10 % of total amount of BOQ.

Signature of client

Signature of contractor