

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 898

Dated: 10.06.2020

SHORT TENDER NOTICE

Sealed Tender is invited from experienced party for **Insulation work on Chilled pipeline of SS from Silo-08 to MMTs via processing section, FBD Patna**. The details scope of work is attached herewith as per **BOQ**.

Interested parties may submit their quotation latest by 25.06.2020 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope "Insulation work on Chilled pipeline of SS from Silo-08 to MMTs , FBD Patna".



Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC
Patnadairy.org

Bill Of Quantities(BOQ) for insulation work on chilled pipeline of SS from silo-08 to MMTs via processing section

Sl. No.	Descriptions of work	Unit	Qty.	Rate	Amount
1	Providing, wrapping and fixing Polyurethane Foam (PUF) of 2 inches thick insulation on SS pipeline of 63 mm diameter and cladding with aluminium metal sheet of 24 gauge on wrapped PUF. All types of tools & tackles, ladders, Bamboos, ropes, screws and any other accessories required during the execution of works have to arrange by party.	M	70		
2	Providing, wrapping and fixing Polyurethane Foam (PUF) of 2 inches thick insulation on SS pipeline of 51 mm diameter and cladding with aluminium metal sheet of 24 gauge on wrapped PUF. All types of tools & tackles, ladders, Bamboos, ropes, screws and any other accessories required during the execution of works have to arrange by party..	M	80		
TOTAL ESTIMATED COST=					
In words:- Rs					

Note:- 1) The above quantity may increase or decrease as per the actual working conditions.