

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 2388,

Dated: 04.09.2020

TENDER NOTICE

Sealed Tender is invited from experienced party for **Civil Repairing work in whole day Booth at RPS More (Satabdi Milk Booth), Rajbanshi Nagar(160-614) and Officer flat milk parlour (160-526) Patna**. The details scope of work is attached herewith as per BOQ.

Interested parties may submit their quotation latest by 19.09.2020 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles "**Civil Repairing work in whole day Booth, Patna**".



Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notice Board, FBD, CFF, HCC
Patnadairy.org

ESTIMATE/Bill Of Quantities(BOQ)

Work-Civil repairing work in whole day booth at RPS More(Satabdi Milk booth)

S.NO	PARTICULARS OF ITEMS	UNIT	NO.	LENGTH(IN M)	WIDTH(IN M)	HEIGHT(N M)	QTY.	Rate as per BSOR 2018	Amount
1	Dismantling floor tiles of size 300x300mm	Sqm	1	4.6	0.2		0.920		
		Sqm	1	7.5	0.38		2.850		
		Sqm	1	7.5	0.45		3.375		
		Sqm	28	0.3	0.3		2.520		
	Stairregion	Sqm	1	1.3	1.4		1.820		
	P186,15.23.1	Total qty (sqm)					11.485	25.5	292.8675
2	Providing and fixing floor tiles of size 300x300mm	Sqm	1	4.6	0.2		0.920		
		Sqm	1	7.5	0.38		2.850		
		Sqm	1	7.5	0.45		3.375		
		Sqm	28	0.3	0.3		2.520		
	Stair region	Sqm	1	1.3	1.4		1.820		
	P149,11.37	Total qty (sqm)					11.485	671	7706.435
3	carriage charge								242.57
TOTAL ESTIMATED COST=									8241.872
TOTAL ESTIMATED COST(Say)=									8242
In words:- Rs Eighteen Thousand Two Hundred Fourty Two Only									

I AGREED & READY TO THIS WORK

S.No		In Numeric	In word
1.0	On the given B.O.Q. rate	%	
	Above the B.O.Q. rate (Present)	%	
	Below the B.O.Q. rate (Present)	%	
Note: Quoted rate should neither be less than 10% of the total estimate cost of BOQ nor it should be more the than 10% of the total estimated cost of BOQ			

(Signature)
31/07/2020

(Signature)

ESTIMATE/Bill Of Quantities(BOQ)

Work-Civil repairing work in whole day booth at Rajbanshinagar(160-614) and at officer flat milk parlour(160-526)

S.NO	PARTICULARS OF ITEMS	UNIT	NO.	LENGTH(IN III)	WIDTH(IN M)	HEIGHT(N M)	QTY.	Rate as per BSOR 2018	Amount
1	Dismantling work in brick wall	CUM	1	2.2	0.25	0.45	0.248		
		Cum	1	1.2	0.125	1.5	0.225		
P185,15.7.4		Total qty.(cum)=					0.473	685.1	323.70975
2	Hacking work at officer flat	Sqm	1	3.8	3		11.4		
P184,14.83		Total qty.(cum)=					11.400	1.3	14.82
3	Full Brick masonry(1:6) upto plinth level	Cum	1	2.2	0.25	0.45	0.248		
P93,15.7.4		Total qty.(cum)=					0.248	4799.20	1187.802
4	Half Brick masonry(1:4)	Sqm	1	2.2	-	1.5	3.3		
P93,6.18.4A+6.19A		Total qty.(cum)=					3.300	671.5	2215.95
5	Brick edge soling on floor for Baising the height of the floor	sqm	1	3.5	2.5		8.750		
P153,11.73		Total qty.(cum)=					8.750	439.8	3848.25
6	Cement concrete flooring of 40mm thick with concrete ingredients ratio of (1:2:4) along with a floating coat of neat cement	sqm	1	3.5	2.5		8.750		
P144,11.3		Total qty.(cum)=					8.750	282.6	2472.75
7	12mm cement mortar plaster(1:4) on interior part	sqm	1	2	-	2	4.000		
7.1	At officer flat booth	sqm	1	3.8	3	-	11.400		
P167,13.11.2		Total qty.(cum)=					15.400	139.9	2154.46
8	15 mm cement mortar plaster(1:5) on exterior part	sqm	1	2		2.3	4.600		
P167,13.12.3		Total qty.(cum)=					4.600	153.1	704.26
9	Neat cement punning at officer flat booth	sqm	1	3.8	3	-	11.400		
P167,13.26		Total qty.(cum)=					11.400	38.6	440.04
10	Carriage charges								3632.72
11	Miscellaneous work for straightening ,aligning and fixing door frame and other items as per site condition								1500.00
TOTAL ESTIMATED COST=									18494.767
TOTAL ESTIMATED COST(Say)=									18495

In words:- Rs Eighteen Thousand Four Hundred Ninty Five Only

I AGREED & READY TO THIS WORK

S.No		In Numeric	In word
1.0	On the given B.O.Q. rate	%	
	Above the B.O.Q. rate (Present)	%	
	Below the B.O.Q. rate (Present)	%	