

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 2446

Dated: 05.09.2020

7

TENDER NOTICE

Sealed Tender is invited from experienced party for **Civil work for Construction of Platform with shed for New Transformer and VCB Panel for Plant, FBD**. The details scope of work is attached herewith as per BOQ.

Interested parties may submit their quotation latest by 20.09.2020 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelop Tiles "**Construction of Platform with shed for New Transformer and VCB Panel at FBD, Patna**".



Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC
Patnadairy.org

Bill of Quantities(BOQ)

WORK:- Civil work for construction of a plateform with shed for new transformer and VCB Panel for plant at FBD

SOR 2018	NAME OF WORK	UNIT	QTY.	RATE	AMOUNT
p-72/2.6	Earth work in excavation for all kinds of soil over areas (exceeding 30 cm in depth , 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m .Disposed soil to be leveled and neatly dressed	CUM	13.536	279.1	3777.898
P-75/2.28	Supplying and filling in plinth with local sand and under floors including watering,ramming,consolidating and dressing complete	CUM	22.56	238.6	5382.816
P-153/11.72	providing designation 100A one brick FLAT soling joints filled with local sand including cost of watering, taxes,royalty all complete as per building specification and direction of E/I	SQM	26.88	277.5	7459.200
p-93/ 6.1.14A	Brick work with bricks of class designation 100A in foundation with cement mortar 1:6(1 cement : 6 coarse sand) upto plinth level	CUM	6.72	4799.2	32250.624
P-87/5.33A. 2.1	Providing and laying in position machine batched,machine mixed and machine vibrated design mix cement concrete of M20 grade with 1:1.5:3(1 cement :1.5 coarse sand :3 graded stone aggregate 20mm nominal size)in tie beam,columns and pile caps excluding the cost of centering,shuttering,finishing and reinforcement upto plinth level	CUM	4.7	5373.1	25253.570
P-167/13.17.2	12 mm cement plaster 1:6(1 cement : 6 coarse sand) on interior of partition wall	SQM	45.28	177.1	8019.088
P-167/13.26	Neat cement punning	SQM	45.28	38.6	1747.808
P-86/5.22	Reinforcement for RCC work including straightening,cutting,bending,placing in position and binding all complete				
P-86/5.22.7A	TMTC-500-8 mm bars	Kg	109.21	77.4	8452.854
P-86/5.22.7B	TMTC-500-10 mm bars	Kg	306.032	76.7	23472.654
P-84/5.9	CENTRING AND SHUTTERING including strutting,propping etc. And removal of form for				
P-84/5.9.1	For foundation,footings etc.	SQM	2.400	186.3	447.120
P-84/5.9.6	For columns	SQM	17.600	425.8	7494.080
P-84/5.9.5	For lintels,beams and bands	SQM	11.2	335.3	3755.360
P-84/5.9.3	For plateform slab	SQM	2.240	362.6	812.224

P-141/10.16.1	steel work in built up tubular trusses from hot finished welded type tubes including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, welded and bolted including special shaped washers etc. Complete	Kg	433.52	88.6	38409.872
FBD/36/582 dated 23-05-2020	Cladding and roofing of crate shed using durashine sheet Zn-Al sheet	sqm	35.6	750	26700
Details attached	Carriage charge		Rs		35409.451
TOTAL ESTIMATED COST=					228844.619
TOTAL ESTIMATED COST(SAY)=					228845

Rs Two Lakh Twenty Eight Thousand Eight Hundred Forty Five only

I AGREE & READY TO DO THIS WORK

S.No.	Particulars	In numeric value (In %)	In words
1.0	ON THE GIVEN B.O.Q RATE		
2.0	ABOVE THE B.O.Q RATE(PRESENT)		
3.0	BELOW THE B.O.Q RATE(PRESENT)		

Signature of client

[Handwritten Signature]
 05.09.2020
 Dy. Manager (Engg.)
 Project: Balancing Dairy
 Project: Dairy Project
 FF: Warisnagar, Padra
 800505

Signature of contractor with seal