

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 3117

Dated: 08.10.2020

TENDER NOTICE

Sealed Tender is invited from experienced party for **Civil work for repairing of whole day milk booth at shastri golambar (160-667) at Rajendra Nagar, Patna**. The details scope of work is attached herewith as per BOQ.

Interested parties may submit their quotation latest by 22.10.2020 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles **“Repairing of whole day milk booth (160-667) at Rajendra Nagar Patna”**.


Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC
Patnadairy.org

Bill of Quantities(BOQ)


WORK:- Civil work for repairing of a whole day milk booth at shastri golambar(160-667) at Rajendra Nagar Patna

S.No.	SOR 2018	NAME OF WORK	UNIT	QTY.	RATE	AMOUNT
1	p-184/14.83	Hacking of Cement Concrete roof	SQM	10.73	1.3	13.95
2	P-144/11.3.1	40mm thick cement concrete flooring(1:2:4)	SQM	10.08	282.6	2848.61
3	P-153/11.73	Providing and laying edge brick soling	SQM	20.62	439.8	9068.68
4	P-167/13.12.4	Plaster 15mm(1:6)	SQM	20.9	145.5	3040.95
5	P-167/13.26	Neat cement punning	SQM	20.9	38.6	806.740
6	Details attached	Carriage charge			Rs	4963.870
TOTAL ESTIMATED COST=						20742.793
TOTAL ESTIMATED COST(SAY)=						20743

Rs Twenty Thousand Seven Hundred Fourty Three only

I AGREE & READY TO DO THIS WORK

		In Numeric	In words
1.O	ON THE GIVEN B.O.Q RATE		
2.O	ABOVE THE B.O.Q RATE(PRESENT)		
3.O	BELOW THE B.O.Q RATE(PRESENT)		


06.10.2020

Signature of client with seal

**Dy. Manager (Engg.)
Feeder Balancing Dairy
Patna Dairy Project
Phulwarisharif, Patna
801505**

Signature of contractor with seal