

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 6132

Dated: 02.02.2021

3

TENDER NOTICE

Sealed Tender is invited from experienced party for **Civil work of Whole day Milk Booth (Code no. 160525) near Auto Stand, Kankarbagh Patna**. The details scope of work is attached herewith as per BOQ.

Interested parties may submit their quotation latest by 15.02.2021 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles "**Civil work of Whole day Milk Booth near Auto Stand, Kankarbagh, Patna**".



Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC
Patnadairy.org

Bill of Quantities(BOQ)

WORK:- Repairing work in whole day milk booth at tempu stand in Kangarbagh

S.No.	SOR 2020	NAME OF WORK	UNIT	QTY.	RATE	AMOUNT
1	P-96/2.28	Supplying and filling in plinth with local sand and under floors including watering,ramming,consolidating and dressing complete	CUM	1.845	281.4	519.183
2	P-184/11.72	providing designation 100A one brick FLAT soling joints filled with local sand including cost of watering, taxes,royalty all complete as per building specification and direction of E/I	SQM	18.27	285.2	5210.604
3	P-99/4.1.2	RCC WORK with 1:1.5:3(1 cement:1.5 coarse sand:3 graded stone aggregate) excludig the cost of centering and shuttering,finishing and reinforcement	CUM	1.178	4380.4	5160.111
4	P-84/5.9	CENTRING AND SHUTTERING including strutting,propping etc. And removal of form for Columns				
5	P-104/5.9.1	Front floor	SQM	0.435	203	88.305
6	P-202/13.11.4	12 mm cement plaster 1:6(1 cement : 6 coarse sand) on interior of partition wall	SQM	38.360	134.5	5159.42
7	P-179/11.37	Providing and laying floor tiles	SQM	10.640	712.2	7577.808
8	P-179/11.36	Providing and laying wall tiles	SQM	16.320	797.5	13015.2
9	P-168/10.5.1	Providing and fixing in position MS door	SQM	2.520	3177.5	8007.3
10	P-174/11.4	Providing and laying IPS of 52 mm thickness	SQM	11.310	456.5	5163.015
11	P-204/13.40A	Providing and applying putty of standard manufacturer	SQM	20.160	121.1	2441.376
12	P-204/13.48.1	Providing and applying paint of standard manufacturer	SQM	53.120	104.7	5561.664
13	P-220/14.83	Hacking work	SQM	41.910	1.4	58.674
14		Dismantling work				
15	P-227/15.56	Old plaster	SQM	28.160	20.3	571.648
16	P-222/15.21	RCC	CUM	0.120	911.4	109.368
17	P-106/5.22.7A	TMTC-500-8 mm bars	Kg	4.345	70.6	306.757
	P-171/10.32.2	MS Angle(40x40x5mm)	Kg	16.5	99.5	1641.750

Carriage Breakup


22.1	P-90/1.4(i)& p 89/2.1	Coarse aggregate	CUM	1.503	2644.06	3974.02
22.2	P-90/1.4.(i)(ii)& p 89/1.1	Coarse sand	CUM	1.86	687.42	1278.60
22.3	P-90/1.4.(i)(iii)& p 89/1.1	Local sand	CUM	1.845	230.46	425.20
22.4	P-92/1.4.(i)(ii)& p 92/1.2	Brick	per Thousand	0.59	899.2	530.53

22.5	P-92/1A(i)& p 91/1.3	Cement & Steel	MT	0.999	214.7	214.49
Difference of cost						
22.6	P-33/2602E-1 2602F	Bricks	per Thousand	590	326.6	192.69
22.7	P-9/036/B- 036/H	Cement(PPC)	MT	0.995	234.6	233.43
23	TOTAL ESTIMATED COST=					67441.140
TOTAL ESTIMATED COST(SAY)=						67441

Rs Sixty Seven Thousand Four Hundred Fourty One Only

I AGREE & READY TO DO THIS WORK

		Numerical value(%)	In words
1.0	ON THE GIVEN B.O.Q RATE		
2.0	ABOVE THE B.O.Q RATE(PRESENT)		
3.0	BELOW THE B.O.Q RATE(PRESENT)		


 Signature of client

Signature of contractor

Dy. Manager (Engg.)
Feeder Balancing Dairy
Patna Dairy Project
Phulwarisharif, Patna
801505