

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 6131

Dated: 02.02.2021

3

TENDER NOTICE

Sealed Tender is invited from experienced party for **Civil work for Floor preparation around transformer area, VCB Panel area and 1010 KVA DG set area at Feeder Balancing Dairy, Patna**. The details scope of work is attached herewith as per BOQ.

Interested parties may submit their quotation latest by 15.02.2021 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles "**Floor preparation around transformer area, VCB Panel area and 1010 KVA DG set area at FBD, Patna**".



Manager (MM)

Enclosure: As above

- Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notice Board, FBD, CFF, HCC
Patnadairy.org

Bill of Quantity (BOQ)

WORK:- Floor preparation around transformer area, VCB panel area and 1010KVA DG set panel area


S.No.	SOR 2020	NAME OF WORK	UNIT	QTY.	RATE	AMOUNT
1	p-222/15.7.4	Demolishing brick work in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 meters lead	CUM	2.1	773.5	1624.350
2	p-93/2.6.1	Earth work in excavation for all kinds of soil over areas (exceeding 30 cm in depth , 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m .Disposed soil to be leveled and neatly dressed	CUM	0.468	314.9	147.373
3	P-96/2.28	Supplying and filling in plinth with local sand and under floors including watering,ramming,consolidating and dressing complete	CUM	83.998	281.4	23637.037
4	P-184/11.72	providing designation 100A one brick FLAT soling joints filled with local sand including cost of watering, taxes,royalty all complete as per building specification and direction of E/I	SQM	121.14	285.2	34549.128
5	p-113/6.18.4A	Half brick work masonry of class designation 100A in superstructure above plinth level with cement mortar 1:4(1 cement : 4 coarse sand) ABOVE PLINTH LEVEL	SQM	22.740	601.1	13669.014
6	P-107/5.33A.1	RCC WORK with 1:1.5:3(1 cement:1.5 coarse sand:3 graded stone aggregate) excludig the cost of centering and shuttering,finishing and reinforcement upto plinth level	CUM	12.153	4689.2	56987.848
7	P-107/5.33A.2.1	RCC WORK with 1:1.5:3(1 cement:1.5 coarse sand:3 graded stone aggregate) excludig the cost of centering and shuttering,finishing and reinforcement above plinth level upto v level	CUM	0.318	5194.8	1651.946
8	P-84/5.9	CENTRING AND SHUTTERING including strutting,propping etc. And removal of form for Columns				
9	P-104/5.9.1	Foundation (pcc)	SQM	0.120	203	24.36
10	P-104/5.9.6	For columns	SQM	3.600	470.6	1694.16
11	P-104/5.9.5	For lintels,beams and bands	SQM	2.28	362.9	827.412
12	P-104/5.9.16.2	Edges of slab	SQM	3.75	557.6	2091
13	P-202/13.11.4	12 mm cement plaster 1:6(1 cement : 6 coarse sand) on interior of partition wall	SQM	65.950	134.5	8870.275
14	FBD/36/582 dated 23-05-2020 including GST	Cladding and roofing of crate shed using durashine sheet Zn-Al sheet	sqm	21	840	17640.000
15	P-106/5.22.7A	TMTC-500-8 mm bars	Kg	405.246	70.6	28610.368
16	P-106/5.22.7B	TMTC-500-10 mm bars	Kg	37.448	69.2	2591.402
Carriage Breakup						
17	P 90/1.4(i)& p . 89/1.1	Coarse aggregate	CUM	10.6	2724.7	28881.82
18	P-90/1.4.(ii)& p 89/1.1	Coarse sand	CUM	6.472	606.78	3927.08
19	P 90/1.4.(i)& p 89/1.1	Local sand	CUM	83.998	230.46	19358.18

20	P-92/1.4,(i)(ii)& p-92/1.2	Brick	per Thousand	5.314	899.2	4778.35
21	P-92/1.4(i)& p-91/1.3	Cement & Steel	MT	4.707	214.7	1010.59
22		Difference of cost				
23	P-33/2602E-2602F	Bricks	per Thousand	5.314	326.6	1735.55
24	P-9/Q367B-0367H	Cement(PSC)	MT	4.265	234.6	1000.57
25		TOTAL ESTIMATED COST=				255307.815
		TOTAL ESTIMATED COST(SAY)=				255308

Rs Two Lakh Fifty Five Thousand Three Hundred Eight Only

I AGREE & READY TO DO THIS WORK

		Numerical value(%)	In words
1.0	ON THE GIVEN B.O.Q RATE		
2.0	ABOVE THE B.O.Q RATE(PRESENT)		
3.0	BELOW THE B.O.Q RATE(PRESENT)		


Signature of client

Signature of contractor

Dy. Manager (Engg.)
Feeder Financing Dairy
Patna Dairy Project
Pnularisharif, Patna
801505