

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 6664

Dated: 26.02.2021

TENDER NOTICE

Sealed Tender is invited from experienced party for **Fabrication of a new milk reception computer cabin of size- 6.5' x 4' at BEN and Barbigha BMC**. The details scope of work is attached herewith as per BOQ.

Interested parties may submit their quotation latest by 12.03.2021 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelop Tiles "**Fabrication work of a Computer cabin of size- 6.5' x 4' at BEN and Barbigha BMC**".



Manager (MM)

Enclosure: As above

- Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC
Patnadairy.org

Bill of Quantities(BOQ)

WORK:- Fabrication of a new milk reception computer cabin of size 6.5'x4' at Fatuha and Ekangarsatrai BMC

S.No	SOR 2020	NAME OF WORK	UNIT	QTY.	RATE	AMOUNT
1	P-305/21.1	Providing and fixing aluminium work for partitions with extruded built up appropriate z section in aluminium snap beading of powder coated aluminium(minimum thickness of powder coating 50 micron) for glazing including necessary filling up the gaps at the junctions i.e at top,bottom and sides with required EPDM rubber/neoprene gasket etc. as per architectural drawings				
2	P-305/21.1.1.2	Providing and fixing partitions from powder coated aluminium of 50 micron(jindal make OR ANY OTHER EQUIVALENT MAKE) for fixed portion	Kg	96.015	414.7	39817.421
3	P-305/21.1.2.2	Providing and fixing partitions from powder coated aluminium of 50 micron(jindal make OR ANY OTHER EQUIVALENT MAKE) for door and windows	Kg	27.439	474.8	13028.037
4	P-306/21.3.2	Providing and fixing glazing in aluminium partitions with EPDM rubber/neoprene gasket etc. Complete as per drawings with float glass panes of 5.5 mm thickness	SQM	13.8	1110.2	15320.76
5	P-307/21.7.2	providing & fixing powder coated aluminium sheet 2.5 mm thick(min. thickness of powder coating 50 micron) machine moulded aluminium covering of approved pattern & design,made out of machine cut aluminium sheet and machine holed for receiving dash fastener,over expansion joints on vertical surfaces/ceiling floors,the fixing on plate in one row on one side of joint at cabin bottom	Kg	84	569	47796
6	p-145/9.100.1	Providing and fixing aluminium handles of 125mm ,ISI marked,anodised(anodic coating not less than grade AC10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc. Complete	Each	4	56.8	227.2
7	p-145/9.103	providing and fixing bright finished brass 100mm mortice latch and lock,ISI marked,with six levers and a pair of anodised (anodic coating not less than grade AC 10 as per IS:1868) aluminium lever handles of approved quality with necessary screws etc. Complete	Each	2	669	1338
8	p-145/9.97.1	Providing and fixing aluminium tower bolts of 300x10mm ,ISI marked,anodised(anodic coating not less than grade AC10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc. Complete	Each	2	111	222
9	p-193/12.45.3	Providing and fixing false ceiling at all height from 12.5 mm thick tapered edge gypsum moisture resistant board including all fitting accessories	Sqm	5	1012.8	5064
10	TOTAL ESTIMATED COST=					122813.418
11	TOTAL ESTIMATED COST(SAY)=					122813
Rs One Lakh Twenty Two Thousand Eight Hundred Thirteen Only						

I AGREE & READY TO DO THIS WORK

		In Numeric	In words
1.0	ON THE GIVEN B.O.Q RATE		
2.0	ABOVE THE B.O.Q RATE(PRESENT)		
3.0	BELOW THE B.O.Q RATE(PRESENT)		

(Signature)
23/04/24

Signature of client with seal
Dy. Manager (Engg.)
Feeder Balancing Dairy
Patna Dairy Project
Phulwarisharif, Patna
801505

Signature of contractor with seal