

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 749

Dated: 28.05.2021

TENDER NOTICE

Sealed Tender is invited from experienced party for **Civil work construction work in condensing unit platform of Bidupur BMC (Hajipur)**. The details scope of work is attached herewith as per BOQ.

Interested parties may submit their quotation latest by 12.06.2021 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles "**Civil work construction work in condensing unit platform of Bidupur BMC**".



Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notice Board, FBD, CFF, HCC
Patnadairy.org

BILL OF QUANTITIES(BOQ)

WORK : Civil repairing works in condensing unit platform OF BIDUPUR BMC
RATES ARE BASED ON BCD SOR-01.07.2020

S.No.	SOR 2020	NAME OF WORK	UNIT	QTY.	RATE	AMOUNT
1	P-222/15.7.4	Demolishing brick work in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 meters lead	CUM	0.513	773.5	396.8055
2	P-96/2.29.1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift upto 1.5 m. All kinds of soil	100SQM	0.128	1272.5	162.88
3	P-174/11.3.1	Cement concrete flooring 1:2:4(1 cement:2 Coarse Sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry,etc. but excluding the cost of nosing of steps etc. complete with 40 mm thick with 20 mm nominal size stone aggregate	SQM	13.23	280.8	3714.984
4	P-184/11.72	providing designation 100A one brick FLAT soling joints filled with local sand including cost of watering, taxes,royalty all complete as per building specification and direction of E/I	SQM	13.125	285.2	3743.25
TOTAL ESTIMATED COST(SAY)(Without Carriage)=						8017.9195
5	Details attached	Carriage charge				
5.1	...do...	Coarse aggregate	Cum	0.451	2590.3	1168.2253
5.2	...do...	Coarse Sand	Cum	0.225	1157.82	260.5095
5.3	...do...	Bricks	Per thousand.	0.424	899.2	381.2608
5.4	...do...	Cement	MT	0.17	214.7	36.499
5.5	...do...	Difference of cost.				
5.6	...do...	Bricks	Per thousand.	0.424	326.6	138.4784
5.7	...do...	Cement(PSC)	MT	0.17	207	35.19
TOTAL Carriage Charge(In Rs)=						2020.163
TOTAL ESTIMATED COST with carriage (SAY)=						10038
Rs Ten Thousand Thirty Eight Only						

I AGREE & READY TO DO THIS WORK

		In Numeric value(%)	In words
1.0	ON THE GIVEN B.O.Q RATE		
2.0	ABOVE THE B.O.Q RATE(PRESENT)		
3.0	BELOW THE B.O.Q RATE(PRESENT)		

Signature of client with seal

Signature of contractor with seal