

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

# PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 819

Dated: 02.06.2021

## TENDER NOTICE

Sealed Tender is invited from experienced party for **Fabrication work of a false ceiling in Laboratory at Feeder Balancing Dairy, Patna**. The details scope of work is attached herewith as per BOQ.

Interested parties may submit their quotation latest by 15.06.2021 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles "**Fabrication work of a false ceiling in Laboratory at FBD**".



Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD  
2) All the legal document i.e. Photo, ID Proof  
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notice Board, FBD, CFF, HCC  
Patnadairy.org

## Bill of Quantities(BOQ)

**WORK:- Fabrication work of a new false ceiling in laboratory at FBD**

S.No	SOR	NAME OF WORK	UNIT	QTY.	RATE	AMOUNT
1	P-193/12.45	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS:277 and consisting of angle cleats of size 25mm wide x 1.6 mm thick with flanges of 27mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5mm x 50 mm long with 6 mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.5mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I channels 45x15x0.9mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450mm centre to centre, shall be fixed in a direction perpendicular to G.I intermediate channel with connecting clips made out of 2.64mm dia x 230mm long G.I wire at every junction, including fixing perimeter channels 0.5mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450mm centre, with 25mm long dry wall screws @ 230mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compounds, jointing tapes, finishing with jointing compound in 3 layers covering upto 150mm on both sides of joint and two coats of suitable primer for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cut outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in charge but excluding the cost of painting with:				
1.1	P-193/12.45.1	12.5mm thick tapered edge gypsum plain board conforming to IS:2095-Part I	sqm	44.120	833	36751.960
TOTAL ESTIMATED COST(In Rs)						36751.960
TOTAL ESTIMATED COST(In Rs)(Say)						36752
Rs Thirty Six Thousand Seven Hundred Fifty Two Only						

I AGREE & READY TO DO THIS WORK

		In Numeric	In words
1.0	ON THE GIVEN B.O.Q RATE		
2.0	ABOVE THE B.O.Q RATE(PRESENT)		
3.0	BELOW THE B.O.Q RATE(PRESENT)		

Signature of client with seal

Signature of contractor with seal

Dy. Manager (Engg.)  
 Feeder Balabaling Dairy  
 Patna Dairy Project  
 Phulwarisharif, Patna  
 801506