

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 4708

Dated: 19.11.2021

२०

TENDER NOTICE

Sealed Tender is invited from experienced party for **civil work for Floor preparation of security cabin at main gate at FBD**. The details scope of work as per BOQ attached herewith.

Interested parties may submit their quotation latest by 03.12.2021 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles "**Floor preparation of security cabin at main gate at FBD, Patna.**"

Bidder must be registered for civil work in Bihar Govt or COMFED, Patna.


19.11.21
Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notice Board, FBD, CFF, HCC
Patnadairy.org

BILL OF QUANTITIES(BOQ)

WORK:- Floor preparation of security cabin at main gate at FBD

S.No	SOR 2020	NAME OF WORK	UNIT	QTY.	RATE	AMOUNT
1	P-96/2.28	Supplying and filling in plinth with local sand and under floors including watering,ramming,consolidating and dressing complete	CUM	4.272	281.4	1202.141
2	P-184/11.72	providing designation 100A one brick FLAT soling joints filled with local sand including cost of watering, taxes,royalty all complete as per building specification and direction of E/I	SQM	21.36	285.2	6091.872
3	P-107/5.33A.1	RCC WORK with 1:1.5:3(1 cement:1.5 coarse sand:3 graded stone aggregate) excludg the cost of centering and shuttering,finishing and reinforcement upto plinth level	CUM	2.136	4689.2	10016.131
4	P-178/11.26.1	20 to 25 Kota stone slab flooring over 20mm(average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete.Base with 1:4(1 cement:4 Coarse sand)	SQM	25.140	1153.8	29006.532
5	P-224/15.23.1	Dismantling tile work of thickness 10 mm to 25 mm in floors laid in cement mortar including stacking material within 50meters lead	SQM	11.200	28.8	322.560
6	P-177/11.20.3	Chequerred precast cement concrete tiles of dark shade using ordinary cement of 22 mm thick with marbie chips of size 6 mm in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing and cleaning etc. complete on 20mm thick bed of cement mortar 1:4(1cement:4 Coarse Sand)	SQM	8.6	742.9	6388.940
7	P-125/8.13	Providing and laying polished Granite stone flooring in required design and patterns,in linear as well as curvilinear portions of the building all complete with 18 mm thick stone slab over 20mm(average) thick base of cement mortar 1:4(1cement:4 coarse sand) laid and jointed with whitw cement slurry admixed with pigment of jet black,cherry red,elite brown,cat eye or equivalent	SQM	1.254	3273.3	4105.946
8	ESTIMATED COST(Without carriage)=					57134.122
	Details attached	Carriage charge				
	a	Graded Stone aggregate 175 km.	Cum.	1.816	2724.70	4,948.055
	b	Coarse sand 45km.	Cum.	1.499	606.78	909.314
	c	Local Sand	Cum.	4.272	230.46	984.525
	d	Bricks 8km	1000No.	0.690	899.20	620.448
	e	Reinforcement (Steel)	Tonne	0.000	214.70	0.000
	f	Cement	Tonne	1.124	214.70	241.323
12	B	Difference of Cost of Materials SAHARSA ZONE				
	I	Bricks	1000No.	0.690	326.60	225.190
	II	Cement	Tonne	1.124	234.60	263.690
13		TOTAL CARRIAGE CHARGE			Rs.	8,192.546
	TOTAL ESTIMATED COST(10+13)=					65326.667
	TOTAL ESTIMATED COST(SAY)=					65327

Rs Sixty Five Thousand Three Hundred Twenty Seven Only

I AGREE & READY TO DO THIS WORK

		In Numeric	In words
1.0	ON THE GIVEN B.O.Q RATE		
2.0	ABOVE THE B.O.Q RATE(PRESENT)		
3.0	BELOW THE B.O.Q RATE(PRESENT)		

Signature of client with seal

Signature of contractor with seal