

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

# PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR:

3195

Dated: 02.09.2022

## TENDER NOTICE

Sealed Tender is invited from experienced party for **Elevation of floor and corresponding increase in existing scrap shed at Hajipur Dairy, Hajipur.** The details scope of work as per BOQ with diagrams attached herewith.

Interested parties may submit their quotation latest by 16.09.2022 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles **“Floor elevation work scrap shed at Hajipur Dairy, Hajipur.”**

Bidder must be registered for civil work in Bihar Govt or COMFED, Patna.

Manager (MM)\

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD  
2) All the legal document i.e. Photo, ID Proof  
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC  
Patnadairy.org

## BILL OF QUANTITIES

**WORK:- Civil work for elevation of floor and corresponding increase in existing scrap shed at Hajipur**

<b>RATES ARE BASED ON BCD SOR-01.01.2022</b>						
S.No	SOR 2020	NAME OF WORK	UNIT	QTY.	RATE	AMOUNT
1	P-231/15.41	Dismantling cement asbestos, celotax or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 meters lead	SQM	70	23.7	1659
2	P-192/11.72	providing designation 100A one brick FLAT soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I	SQM	58.5	283.3	16573.05
3	P-104/4.1.5	Providing and laying in position cement concrete of grade 1:3:6(1Coarse aggregate:3 coarse sand:6 Cement)	CUM	4.725	3434	16225.65
4	P-120/6.18.4A+6.19A	Half brick masonry with bricks of class designation 100A above plinth in cement mortar 1:4(1 cement:4 Coarse sand)	SQM	38.25	689	26354.25
5	P-114/5.33A.2	RCC WORK with 1:1.5:3(1 cement:1.5 coarse sand:3 graded stone aggregate) excludig the cost of centering and shuttering, finishing and reinforcement above plinth level upto v level	CUM			
6	P-114/5.33A.2.1	walls, columns, pillars, posts and struts	CUM	0.094	5293.5	496.266
7	P-114/5.33A.2.2	Beams, Girders, bressumers, cantilevers, suspended floors, lintel roofs and staircases including spiral staircases, shelves	CUM	1.59	5677.2	9048.0375
8	P-110/5.9	CENTRING AND SHUTTERING including strutting, propping etc. And removal of form for Columns				
9	P-110/5.9.6	For columns	SQM	1.500	494.4	741.600
10	P-110/5.9.5	For lintels, beams and bands	SQM	25.50	404.7	10319.850
11	P-208/13.11.4	12 mm cement plaster 1:6(1 cement : 6 coarse sand) on exterior of partition wall	SQM	231.000	141.5	32686.500
12	P-208/13.26	Neat cement punning	SQM	25.5	40.5	1032.750
13	P-112/5.22.7A	TMTC-500-8 mm bars	Kg	103.6915	94.5	9798.842
14	P-112/5.22.7B	TMTC-500-10 mm bars	Kg	237.77	92.6	22017.502
15	P-176/10.16.1	steel work in built up tubular(round, square or rectangular hollow tubes etc.) trusses etc. including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, welded and bolted including special shaped washers etc. Complete in hot finished welded type tubes	Kg	42.048	123.9	5209.7472

*[Signature]*  
02/06/2022

*[Signature]*

16	P-195/12.10.1	Providing asbestos cement 6 mm thick corrugated sheets roofing and fixing with G.I Jor L hooks BOLTS AND NUTS 8 MM DIA. G.I PLAIN AND BITUMEN WASHERS COMPLETE excluding the cost of purlins,rafters and trusses corrugated sheet upto 60 degree pitch	sqm	5	371.7	1858.5
TOTAL Estimated Cost (WITHOUT CARRIAGE)						154021.544
<b>Carriage of materials &amp; difference of cost of materials</b>						
17	A	Carriage of Materials				
	a	Graded Stone aggregate 175 km.	Cum.	5.451	3331.10	18,156.577
	b	Coarse sand 45km.	Cum.	7.562	1027.10	7,766.619
	c	Local Sand	Cum.	0.000	-	
	d	Bricks 8km	1000No.	4.250	1177.60	5,005.174
	e	Reinforcement (Steel)	Tonne	0.341	243.70	83.214
	f	Cement	Tonne	3.239	243.70	789.229
18	B	Difference of Cost of Materials SAHARSA ZONE				0.000
	I	Bricks	1000No.	4.250	317.40	1,349.051
	II	Cement	Tonne	3.239	232.30	752.310
TOTAL CARRIAGE CHARGE				Rs.		33,902.174
TOTAL ESTIMATED COST=						187923.718
TOTAL ESTIMATED COST(SAY)=						187924
<b>Rs One Lakh Eighty Seven Thousand Nine Hundred Twenty Four Only</b>						

I AGREE & READY TO DO THIS WORK

		In Numeric	In words
1.O	ON THE GIVEN B.O.Q RATE		
2.O	ABOVE THE B.O.Q RATE(PRESENT)		
3.O	BELOW THE B.O.Q RATE(PRESENT)		

Signature of client with seal

Signature of contractor with seal

  
08/06/2022