

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

VPDUSS-SOP-8.5.1.2-01.F02

PDP:PUR:HCC 117

Dated 05.04.2023

Sub: Work for Drawing soft water line from new soft water silos(2 nos) each of 1.0 lakh litre capacity Installed in the area of 4.0LLPD automatic dairy plant up to 30MTPD powder plant at Hajipur Dairy

Dear sir,

We are interested in work for Work for Drawing soft water line from new soft water silos(2 nos) each of 1.0 lakh litre capacity Installed in the area of 4.0LLPD automatic dairy plant up to 30MTPD powder plant at Hajipur Dairy. In case you can supply the same, you may send your quotation in sealed cover addressed to the Managing Director address given above superscribing on the top of the envelop quotation **Drawing soft Water line at HCC** so as to reached on or before **15.04.2023**.

All rates must be F.O.R. – HCC, Hajipur on door delivery basis.

<i>Sl no</i>	<i>Description of required works to be done</i>	<i>Quantity of work</i>
1	Labor charge for fabrication of Mild steel supports (at 8.0 M height) - total 09 nos All materials shall be provided by dairy but complete with all consumables & and all labor @ Rs 1,500.00 Each	01 job (complete with all materials ,labor & tools)
2	Labor charge for drawing soft water GI pipe lines of 4 " dia at 8.0 M height with all consumables & tools. Total - 48 M. Pipes & fittings will be provided by Dairy @ Rs 800.00 PerM	01 job (complete with labor & tools)
3	Labor charge for fabrication of header with 8 " / 6 " dia GI pipe , fitting of 4 " dia NRV - 02 nos & 4" dia valves - 2 nos as required . All materials will be provided by dairy .	01 job (complete with labor & tools)
4	Labor charge for fabrication of MS frame for installing 02 pumps each of 15.0 HP near soft water silos . All materials will be provided by dairy	01 job (complete with labor & tools)
5	Labor charge for shifting after dismantling of 02 nos water pumps each of 15.0 HP from powder plant to soft water silos site	01 job (complete with labor & tools)
6	Laying of cable tray at height of 8.0 M for 15 HP pumps - Total 8 M length	Do
7	Labor charge for dismantling of 4 " dia butter fly valve in powder plant	Do
8	Labor charge for fitting & fixing of 4 " dia butter fly valve near soft water silos - 4 nos and other allied works for making 3 phase connection to these motors and any other works required at site during execution of works	01 job (complete with labor & tools)

Thanking you

Manager (MM)