

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

VPDUSS-SOP-8.5.1.2-01.F02

PDP:PUR:HCC 745

Dated 08.05.2023

Reminder of Enquiry no. PDP:PUR:HCC 300 dated 13.04.2023

Sub: Work for Creation of LASSI Preparation section in 1.0LLPD Old dairy Plant Hajipur

Dear sir,

We are interested in work for Creation of LASSI Preparation section in 1.0LLPD Old dairy Plant at Hajipur. In case you can supply the same, you may send your quotation in sealed cover addressed to the Managing Director address given above superscribing on the top of the envelop quotation **LASSI Preparation Section at HCC** so as to reached on or before **20.05.2023**.

All rates must be F.O.R. – HCC, Hajipur on door delivery basis.

Sl no	Description of required works to be done	Quantity of work
1	Labor charge for Dismantling of pipe lines valves ,Unions etc from the 5 .0 KL milk storage tank in powder plant and shifting the same to proposed curd /lassi preparation room of old 1.0 LLPD dairy plant.	01 job (complete with all shifting tools & labor)
2	Labor charge for insulating the 5 KL tank with 60 mm thick PUF panels of 40 Kg /Cm2 density .Then providing 2 mm thick SS 304 sheet over PUF insulation to make the tank insulated then Polishing the outer sheet for smooth finish. Work shall be complete with all required materials ,labor , tools & tackles	01 job (complete with all materials ,labor & tools)
3	Labor charge for dismantling ,shifting of one set of LASSI packing machine with overhead tank of 500 Litre approx. capacity from Patna dairy to Hajipur dairy , then installation of the same at Hajipur dairy .This work also includes labor cost for fabrication of working platform,laying of cable tray with supports for connection ,(materials will be provided by Dairy)	01 job (complete with labor & tools)
4	Labor charge for installtion of SS pipe lines from lassi preparation room to packing machine complete with required supports ,All required materials , labor & tools tackles)	01 job (complete with labor & tools)
5	Labor charge for installtion of SS pipe lines from lassi preparation room to packing machine for CIP ,complete with labor & tools tackles) Materials will be provided by dairy.	01 job (complete with labor & tools)
6	Labor charge for installtion of GI pipe lines for normal & soft water lines from lassi preparation room to packing machine ,complete with labor & tools tackles) Materials will be provided by dairy.	Do

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

VPDUSS-SOP-8.5.1.2-01.F02

7	Labor charge for Laying of cable over tray at a height of 5.0 M along with clamping . Cable of required size & lugs will be provided by dairy)	Do
8	Labor charge for shifting of electrical panel existing in lassi preparation room to existing processing section and reconnecting with power panel to make it charged.	01 job (complete with labor & tools)
9	Labor charge for dismantling & shifting of sugar vat with all existing connections along with filter at an height of 7.0 M from powder plant to processing section.	01 job (complete with labor & tools)
10	Labor charge for installation of Sugar vat at required place , making connection of water & steam lines ,installtion of pumps, filters at a height of about 5.0 M.All required Materials will be provided by dairy.	01 job (complete with labor & tools)
11	Any other labor work required for installation of sugar vat & Lassi storage tank and Lassi packing machine	01 job (complete with labor & tools)

Thanking you



Manager (MM)