

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

# PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 1939

Dated: 24.06.2023

## TENDER NOTICE

Sealed Tender is invited from experienced party for **Repairing of the wall of Admn Section at Feeder Balancing Dairy, Patna.** The details scope of work as per BOQ attached herewith.

Interested parties may submit their quotation latest by 05.07.2023 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelop Tiles **“Repairing of the wall of Admn Section at FBD, Patna.”**

Bidder must be registered for civil work in Bihar Govt or COMFED, Patna.



Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD  
2) All the legal document i.e. Photo, ID Proof  
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC  
Patnadairy.org

**VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD.**

(Patna Dairy Project)

Feeder Balancing Dairy COMPLEX, PHULWARISHARIF, Patna-801505)

An ISO 22000:2005 Certified Organization)

Phone: 2252553, 2252542, 2251622, Fax:0612-2250325

E-mail: Vpmunin@gmail.com / vpmu.engg@gmail.com


GST no.-10AAAAV8463B1ZV

Bill of Quantities (BOQ)								
Work:- Repairing of the wall of Admin section								
RATES ARE BASED ON BSOR 2022								
S.No.	BSOR 2022	Description of works	Length (m)	Height (m)	Quantity (sqm)	Rate Rs per sqm	Amount (In Rs)	
1	P - 188/ 11.46.2	Dismantling Old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	4.2	2	8.4	21.7	182.28	
2	P - 233/ 15.56	Providing and laying Vitrified tiles (thickness specified manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed cement mortar 1:3 ( 1 cement : 3 coarse sand ), including grouting the joint with white cement & matching pigments etc. complete. Size of tile 600 x 600 mm	4.2	2	8.4	1191.8	10011.12	
3		Carriage Charges						
		Plastering of 12 mm thick with 1:3 cement mortar						
a		Coarse Sand (0.01548 x 8.4)	0.13 cum			1258.32	163.58	
b		Cement (0.0051 x 8.4)	0.042 MT			492.75	20.7	
		Difference of costs						
		Cement (0.0051 x 8.4)	0.042 MT			204.7	8.59	
		Total ( In Rs ) =						10386.27
		Rounding off ( In Rs )						10386.00
		<b>Rs. Ten Thousand Three Hundred And Eighty Six Only.</b>						

**I AGREE & READY TO DO THIS WORK**

1.0	ON THE GIVEN B.O.Q. RATE	%	
2.0	ABOVE THE B.O.Q. RATE (PRESENT)	%	
3.0	BELOW THE B.O.Q. RATE (PRESENT)	%	

  
23/06/2023  
Signature of client

  
23/06/2023

Signature of contractor