

**VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD**  
**PATNA DAIRY PROJECT**

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

An ISO 22000:2005 Certified Organisation

Phone 0612-2252553,2252542, 2251622, Fax 2250325

E.mail:vpmu.pur@gmail.com

GST no. 10AAAAV8463B1ZV

**Short Tender Notice**

PDP:PUR:FBD: 2796

Dated: 18.07.2024

Sealed tenders are invited from civil contractors registered with Building Construction works Department, Rural Works Department, Water Resource Department, Government of Bihar OR registered with COMFED in suitable class for the civil work as given below :-

Sl no.	Name of Work	Estimated Cost (In Rs.)	Amount of EMD (In Rs.)	Cost of BOQ ( In Rs.)	Time of Completion
	<b>Civil construction work for casting pre-fabricated concrete pillars at Newly demarcated Land at Chhapra by VPMU, Patna Dairy Project, Patna. The details scope of work as per BOQ and diagrams attached herewith</b>	5,97,691.00	11960.00	1200.00	45 days

- (1) Tender document can be obtained from the Cashier at office (Patna Dairy Project), VPDUSS Ltd during office hours OR it may be downloaded from website – [www.patnadairy.org](http://www.patnadairy.org) up to 05.08.2024 at 3.00 pm. Downloaded BOQ must be accompany with DD of BOQ Cost. DD of any nationalized bank shall be submitted in favour of “Vaishal Patliputra Dugdh Utpadak Sahkari Sangh Ltd.”, Payable at Patna
  - (2) Contractors who down load the tender and those who purchase the tender / BOQ directly from office at Patna Dairy Project, both will send their completed tender in a sealed envelope through registered post or through courier to Purchase section at Patna Dairy Project address.
  - (3) Last date of receipt of completed tender – 06.08.2024 up to 3:00 pm. Tenders received after due date & time shall not to be considered.
  - (4) Date of opening all received tenders-07.08.2024 at 3:00pm in the presence of the tenders of their authorized agent in the office of Patna Dairy Project, VPMU.
  - (5) Tenders received after due date & time shall not be considered.
- Undersigned reserves the right to extend the dates OR cancel the tender.

Managing Director

# Bill OF QUANTITY FOR

**WORK:-Civil Construction Work Of Casting Pre-Fabricated Concrete Pillars At Newly Demarcated Land At Chapra by V.P.M.U , PATNA.**

## ABSTRACT OF COST

S.I.no	BSOR - 2022	Description of works	Unit	Qty	Rate	Amount (Rs)
1	P - 303 / 20.3A.1	Making 25 cm (10"0 dia bore up to 4 mtr depth below ground with hand auger of approved quality in ordinary soil (vide classification of soil item A) trur to plumb and without eccentricity in any stage of operation and disposal of the excavated earth up to 50 mtr , Lead including all lifts , all complete as per approved design and direction of E/I Details of cost for 4 piles of 4 m = 16 mtrs depth)	METRE	228.60	178.30	40759.38
4	P-109/5.1.2	Providing & laying in position specified grade of R.C.C. excluding the cost of centring , & shuttering , finishing & reinforcement All work up to plinth level (1:1.5:3) (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 rr , m nominal size)	CUM	24.572	4688.30	115202.08
5	P - 110 / 5.9.1	Centring & shuttering including strutting , propping etc And removal form for foundation, footings base of columns etc for mass concrete	SQM	246.870	211.60	52237.69
7	P 112/ 5.22.7A	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated barsTMTC-500-8mm dia	Kg	2594.20	94.50	245152.09
A		TOTAL				453351.24

B	CARRIAGE CALCULATION	Unit	Qty	Rate	Amount (Rs)
(i)	Bricks(8 KM)	% 0Nos	0	1053.35	0.00
( ii )	Local sand(3 KM)	CUM	0.00	322.79	0.00
( iii )	Coarse sand(58 km)	CUM	10.4432	732.71	7651.84
( iv )	Stone chips(175 km)	CUM	20.8864	4717.08	98522.88
(v)	Cement & Reinforcement(3 KM)	MT	12.4231	492.75	6121.48
	TOTAL				112296.20

C	Difference of cost	Unit	Qty	Rate	Amount (Rs)
( i )	Bricks	% 0Nos	0.0	1590.97	0.00
( ii )	Cement	MT	9.8289	166.51	1636.61
	TOTAL				1636.61

15	TOTAL SUM IN RUPEES(A+B+C) =				567284.05
16	Add Gst as per Govt. Of Bihar 5.36 % as PWD Circular No. 5751 dated 18.07.2023 IN RUPEES				30406.425
17	So final BOQ value in Rupees = (Sum of 15&16)				597690.475
18	TOTAL APPROXIMATE VALUE IN RUPEES				597691

IN WORDS (Five Lakh Ninety Seven Thousand Six Hundred and Ninety One only with GST)

S.L.	I AM AGREE TO DO THIS WORKS:	In %	In Word
1	On The BOQ Rate		
2	Below The Given Rate in %		
3	Above The Given Rate In %		
4	SIGNATURE OF CONTRACTOR	SIGNATURE OF E/I	