

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

# PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: CFF

2078

Dated: 21.06.2024


## Reminder TENDER NOTICE

Sealed Tender is invited from experienced party for **Civil construction work for Removing old False Ceiling and Installation New False Ceiling at Cattle Feed Plant, Jagdeopath, Patna.** The details scope of work as per BOQ attached herewith.

Interested parties may submit their quotation latest by 29.06.2024 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelop Tiles “**Removing old False Ceiling and Installation New False Ceiling at CFF.**”

Bidder must be registered for civil work in Bihar Govt or COMFED, Patna.

Thanking you

  
Manager (MM)

21/06/2024

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD  
2) All the legal document i.e. Photo, ID Proof  
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC  
Patnadairy.org

**REMOVING OLD FALSE CEILING AND INSTALLING NEW FALSE CEILING AT CATTLE FEED PLANT  
(JAGDEO PATH), UNDER PATNA DAIRY PROJECT, PATNA.**

SI	DESCRIPTION OF WORK	NO	L	w	QUANTITY	RATE	AMOUNT
BSOR - 2022							
12.52 x	Providing and fixing tiled false ceiling of specified materials of size 595x595mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections ( galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200 x 600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanized butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.						
12.52x.1	GI Metal Ceiling Lay in plain Tegular edge Global white color tiles of size 595x595 mm, and 0.5 mm thick with 8 mm drop; made of G I sheet having galvanizing of 100 gms. / sqm. (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending.	1	9.70	3.60	34.92	1348.40	Rs. 47,086.13
15.57 + 13.57	Dismantling aluminum / Gypsum /PVC profile sheet with angle cleates & others old accessories of false ceiling including of unserviceable surplus material and stacking of serviceable material within 50 m lead and all scaffolding needs to remove the old materials as per directed by Engineer -in- charge.	1	9.70	3.60	34.92	68.10	Rs. 2,378.05
<b>TOTAL SUM</b>							<b>Rs. 49,464.18</b>
TOTAL SUM IN WORDS (ROUND OFF)- Forty Nine Thousand Four Hundred and Sixty Four Only With Gst.							<b>Rs 49,464.00</b>
	<b>I AM AGREE TO DO THIS WORKS:</b>	<b>IN %</b>				<b>IN WORD</b>	
1	ON THE BOQ RATE						
2	BELOW THE GIVEN RATE (IN %)						
3	ABOVE THE GIVEN RATE (IN %)						
SIGNATURE OF CONTRACTOR					SIGNATURE OF E/I		